



**NOTES:**

1. SAFE PEDESTRIAN ACCESS MUST BE PROVIDED AROUND WORK AREA.
2. PERMANENT IMPROVEMENTS SHALL BE INSTALLED WITHIN 5 DAYS OF TRENCHING.
3. ENTIRE SIDEWALK PANEL MUST BE SAWCUT AND REMOVED AT SCORE MARKS.
4. INSTALL MANUFACTURED CONDUIT CHAIRS BETWEEN CONDUITS IF MORE THAN ONE CONDUIT IS PLACED IN TRENCH.
5. CL II AB, 95% RELATIVE COMPACTION MAY BE USED IN LIEU OF TOP 3 1/2" OF SAND/CEMENT SLURRY.



CITY OF CAMPBELL  
PUBLIC WORKS DEPARTMENT

APPROVED BY:

*AO*  
AMY OLAY, P.E.  
CITY ENGINEER

DATE:

3/14/22

SIGNAL, LIGHTING &  
ELECTRICAL CONDUIT  
INSTALLATION - TRENCH LAID  
CONDUIT IN WALKWAY AREAS

J./DETAILS/CAD/E16

DETAIL  
NO.

E-16

NTS